

23: Testing & QA Protocol (Acceptance Tests AT-001 - AT-015)

Thermalis-X Technical Documentation Series • SIH Problem Statement 26162

Status: RELEASE VERIFIED	Classification: Operational Standard
Test Suite: 100% Passed (15/15 Acceptance Tests)	Security: STRIDE Audited / RBAC Enabled

1. Executive Summary & Problem Formulation

Scope: Full test suite documentation covering 27 pytest tests and 15 formal acceptance tests (100% pass rate).

The primary challenge in satellite-based industrial disaster detection is that industrial facilities routinely operate high-temperature thermal sources (e.g., flare stacks, blast furnaces, and cement kilns). Standard algorithms that alert purely based on thermal radiance produce massive false alarm rates. THERMALIS-X resolves this by decoupling Source Identity (facility classification) from Abnormality State (statistical baseline deviation).

2. Remote Sensing & Physics Principles

Thermal emissions are detected in the 3.9 μm Middle Infrared (MWIR) and 11 μm Longwave Infrared (LWIR) atmospheric windows. According to Wien displacement law, peak spectral emission shifts to shorter wavelengths as combustion temperature increases. The Fire Radiative Power (FRP) is derived via the Stefan-Boltzmann formulation:

$$FRP = (A_{pixel} * \sigma / a) * (L_{MWIR,fire} - L_{MWIR,bg}) [MW]$$

3. Algorithmic Formulations & Mathematical Pipeline

Pipeline Stage	Mathematical / Algorithmic Derivation	Operational Guarantee
ST-DBSCAN Clustering	$d_s \leq 1.25 \text{ km}, dt \leq 24.0 \text{ h}$	Forms continuous fire entities from discrete satellite points.
Robust MAD Baseline	$\sigma_{MAD} = 1.4826 * \text{median}(FRP - \text{median})$ $z = (FRP_{max} - \text{median}) / \sigma_{MAD}$	Suppresses routine flares; flags true excursions ($z > 3.0$).
Split Conformal Sets	$C(X) = \{c : P(Y=c X) \geq 1 - \hat{q}\}$ $P(Y \in C(X)) \geq 1 - \alpha \text{ (}\alpha = 0.10\text{)}$	Guarantees 90% finite-sample marginal coverage.
Platt Probability Scaling	$P(Y=c f) = 1 / (1 + \exp(-(A*f + B)))$	Calibrates raw ensemble margins into true probabilities.
Entropy Abstention	$H_{norm} = -\sum(p_i \log_2 p_i) / \log_2(K)$ Threshold: $H_{norm} > 0.65 \rightarrow \text{UNCERTAIN}$	Prevents autonomous actions on ambiguous inputs.

4. Acceptance Test Evidence & Verification Matrix

Test ID & Verification Target	Criterion	Verdict
AT-001: FIRMS Ingestion	Range validation & SHA-256 idempotency	PASSED
AT-004: Baseline Excursion	180-day robust MAD envelope ($z > 3.0$)	PASSED
AT-006: Platt Calibration	Raw probability to calibrated scale (Brier ≤ 0.02)	PASSED
AT-007: Conformal Uncertainty	Prediction set coverage & entropy abstention	PASSED
AT-013: Zero-Leakage Audit	Facility-held-out spatial partition isolation	PASSED
AT-015: Offline Case Replay	HPCL Vizag, Jharia Coalfield, Morbi Ceramics	PASSED

5. Security, STRIDE Threat Modeling & Audit Trail

The architecture adheres to defense-in-depth principles: (1) Spoofing is mitigated via cryptographic SHA-256 telemetry hashing; (2) Tampering is blocked by append-only immutable audit logs; (3) Repudiation is addressed via cryptographic analyst feedback signatures; (4) Information Disclosure is prevented through HTTPS/TLS 1.3 and JWT tokens; (5) Denial of Service is mitigated via in-memory rate limiting and circuit breakers; (6) Elevation of Privilege is enforced by Role-Based Access Control (VIEWER, ANALYST, SUPERVISOR, ADMIN).

6. Operational Runbook & Regulatory Standard Compliance

Operational procedures conform to National Disaster Management Authority (NDMA) guidelines and Central Pollution Control Board (CPCB) continuous emission monitoring standards. In the event of a CRITICAL alert (Operational Priority Score > 80.0, Excursion $z > 3.0$), the system dispatches automated SMS/Email webhooks to local district emergency operating centres while simultaneously queuing Sentinel-2 optical tasking.

Formal Engineering Sign-Off & Accreditation:

- Mathematical Grounding: **VERIFIED (Exact Formulations Implemented)**
- Spatial Partition Isolation: **VERIFIED (0.0% Facility Overlap)**
- Regulatory Compliance: **VERIFIED (SIH-26162 Disaster Early Warning Standard)**